



RECEIVED

MAY 19 2020

Post Oak Savannah

Southwest Milam Water Supply Corporation

706 E. Cameron Ave.
Rockdale, TX 76567
(512) 446-2604

May 19, 2020

Mr. Gary Westbrook
POS-GCD, General Manager
P.O. Box 92
Milano, Texas 76556

Dear Mr. Westbrook,

The SW Milam Water Board of Directors is requesting to downsize the scope of our 2020 Grant project to better match the funding provided by POS-GCD. We propose to commit the same amount of match funding (\$45,000.00) to the project, this added to the grant amount of \$ 135,714.00, for an estimated total project cost of \$ 180,714.00.

Please review the attached documents, if you need additional information, we will gladly accommodate your request.

Sincerely,

Ken Hall
General Manager
512-446-2604
Ken.hall@swmilamwater.org

WATER LINE CONSTRUCTION


New Water Lines in the Praesel Addition - Phase 2

Bid Item	Description	Quantity	Unit Price	Total Price
1	6" PVC Water Line	1,276	\$30.00	\$38,280
2	4" PVC Water Line	1,120	\$25.00	\$28,000.00
3	6" Gate Valve	2	\$1,500.00	\$3,000.00
4	4" Gate Valve	2	\$1,250.00	\$2,500.00
5	Tie-in 3/4" Mtr w/ Reg and New Serv Ln	16	\$2,750.00	\$44,000.00
6	Tie-in 3/4" Mtr w/ Reg to new WL (TS thru Angle Stop)	1	\$1,000.00	\$1,000.00
7	1-1/2" Poly Service Lines for Long Serv	150	\$20.00	\$3,000.00
8	4" Uncased BORE for Conc Dwy	80	\$80.00	\$6,400.00
9	Open Cut Grav Dwys with Grav Rpr	155	\$15.00	\$2,325.00
10	3" PVC - BORE for Long Serv	120	\$60.00	\$7,200.00
11	2" Flush Valve	1	\$1,500.00	\$1,500.00
12	Tie-in to ex. 6" Water Lines	3	\$2,500.00	\$7,500
13	Asphalt Pmnt Repair for Cty Rds/Dwys	40	\$30.00	\$1,200.00
14	Trench Protection	2,396	\$2.00	\$4,792.00
15	Brush Clearing & Disposal	150	\$50.00	\$7,500.00
Construction Total:				\$158,197.00
Engineering (10%):				\$15,820
Inspection (3%):				\$4,745.91
Contingency				\$ 1,951.09

Project Total \$ 180,714.00



- NOTE:
1. PROPOSED PHASE 2 IMPROVEMENTS ARE SHOWN IN BLUE LINES WHERE ESTIMATED TO BE 25' PAV. CROSSING FOR PRIVATE GRAVEL DRIVEWAYS. ESTIMATED AT 15 LF EACH. ROADS WERE ESTIMATED AT 30 LF.
 2. IMPROVEMENTS ARE SHOWN IN BLUE LINES WHERE ESTIMATED TO BE 25' PAV. CROSSING FOR PRIVATE GRAVEL DRIVEWAYS. ESTIMATED AT 15 LF EACH. ROADS WERE ESTIMATED AT 30 LF.
 3. PRIVATE GRAVEL DRIVEWAYS ESTIMATED AT 15 LF EACH. ROADS WERE ESTIMATED AT 30 LF.
 4. ROADS WERE ESTIMATED AT 30 LF.



**SOUTHWEST MILAM WSC
2020 POST OAK SAVANNAH GRANT PHASE 2
PRAESEL, TEXAS**



SHEET TITLE
OVERALL PLAN

DATE 08/14/20
DATE 08/14/20

1

REVISIONS

NO.	DATE	DESCRIPTION

DRAWN BY: JG
CHECKED BY: M
BEFCO JOB NO: 18-253
DATE: 7/17/20
SCALE: 1" = 100'